



Capabilities: DEPTH RATING 18,000'

Draw Works

OIME SL 1500 1-1/4 DL

Brake

PARMAC 342 Hydromatic

Engines

(3) CAT 3412 Engines, S/Ns-81Z11431 & 81708039

Mast

PYRAMID 146 x 23' 815,000# SHL w/6-Sheave Crown

Substructure

PYRAMID 22.5' KB Swing-Up

Pumps

BREWSTER B-1300T, S/N-13P006, p/b CAT 3512, S/N-49Y00979, w/5" x 6" Charge Pump (Rebuilt)

OILWELL PT1100A, S/N-P199A61, p/b CAT 3508, S/N-95Y01254, w/5" x 6" Charge Pump (Rebuilt)

5-1/4" x 44' Hex Kelly w/Hydraulic Kelly Spinner



Travelling Equipment

SOWA 350-Ton Block/Hook Combination w/(5) Sheaves

Well Control Equipment

HYDRIL GK 11" 10,000 PSI Annular Blowout Preventer
CAMERON Type U 11" 10,000 PSI Double Blowout Preventer
CAMERON Type U 11" 10,000 PSI Single Blowout Preventer
CRESS SPECIALTIES 6-Station Accumulator Unit
WKM HCR 4-1/16" 10,000 PSI Choke Manifold
WKM 4-1/16" Manual Choke Manifold

Rig Houses

ALBERTA LABOUR 12'W x 54'L Toolpusher's Trailer, S/N-00681, w/(2) Bedrooms, (2) Bathrooms, Full Kitchen, (2) Separate Office Areas, Insulated, Skidded
1998 ALBERTA FAB 10'W x 54'L Toolpusher's Trailer

8'W x 38'L Doghouse
10'W x 48'L Parts/Change House
12'W x 40'L Mud House w/(5) 5" x 8" Centrifugal Pumps

Rotating Equipment

PYRAMID HACKER 275 Rotary Table
GARDNER-DENVER 400-Ton Swivel

Water/Fuel Tanks

10'W x 40'L 400-Barrel Water Tank
8'W x 33'L 12,300-Gallon Fuel Tank
8'W x 24'L 7000-Gallon Fuel Tank
150 HP Boiler (In Deck, New 2006)



Generators

(2) CAT 3412 550 KW, S/Ns-6FA67035 & 6FA65093
GD Electra Saver II Air Compressor, 480-Volt, p/b Diesel Engine
GD PL-Series Air Compressor p/b Diesel Engine
MUD SYSTEM
(5) 5" x 6" Centrifugals w/60 HP Electric Motor
3-Pit System w/(8) Mud Agitators, 1800-Barrel System, 12'W x 8'H x 46'L
GALLAGHER 5" x 6" Pit Pump
(7) RADICON Mud Mixers, Each p/b 10 HP Motor
(2) DOUBLE LIFE Linear Shale Shakers
SWACO 2-Cone Desander
DOUBLE LIFE 8-Cone Desilter

Handling Tools

Hydraulic Pipe Spinners, Makeup & Breakout Catheads, (2) Hydraulic Winches, Air Winch

Auxiliary Equipment

TOTCO 700,000# Capacity Weight Indicator, VARCO Bushing

Drill Pipe

(140 Joints) 4-1/2", 16.60 Lb, Grade S-135, 6-1/8", HB & PC
(250 Joints) 4-1/2", 16.60 Lb., Grade X-95, 6-1/4", HB, PC

Drill Collars

(24) 6-1/2" x 4-1/2'XH Drill Collars (New)
(2) 8" x 6-5/8"Reg Drill Collars

Price and Payment condition:



In US Dollars 14 650 000,00 (fourteen millions six hundred fifty thousand US \$)

Delivery Terms: FCO Texas

Packing ready for over see transport.
Inspection on the place prior to delivery.

Payment:

Deposit for 30 days prior to inspection in amount of 1% of the total amount (140 000US \$) that will be include in the final price.

Rest of the amount has to be secured by irrevocable, transferable, confirmed Letter of Credit, or acceptable Bank Guaranty with payment of the rest amount by wire transfer till seven days upon inspection.

Or

By irrevocable, transferable Letter of Credit 100% full amount to be issued immediately prior to inspection. Such L/C to be irrevocable transferable payable 5 Days date of inspection and against presentations of documents including inspection Certificate to our Bank counters.

Include:

Preparation of all relevant documents for export
Transport organization (payment not include)
Follow delivery on the end place.
Support for equipment assembling and start up.

Validity :

This offer is valid for 7 days date of this offer.

For any further information do not hesitate to contact us

Sincerely



Petar Opacic













